



P.O. Box 683
Clint, Texas 79836

Phone (915) 851-0304 • Fax (915) 851-9000

Bid #2016-0204

West Valley Fire Station

Burn Pad

- **Project Overview**

Contractor will need to furnish labor and materials for bid items listed below. A performance bond and permit included.

- 100FT. X 30FT. 6" concrete slab with 1/2" rebars 16"OC both ways 4000 PSI concrete.
- Cut existing curb at adjoining existing slab and run electrical line from existing panel and install two (2) pole lights on existing light poles. Lights must be LED and DLC compliant.
- Build two 20FT. X 20FT. concrete bins for burnt wood and unused wood. Walls will need to be 9" thick with ½ rebars 16" OC both ways 8FT. tall 100 LN FT.

All work must have a manufactures warranty and one year labor warranty. All city permits must be included.

Please schedule a date and time to see the facility with Valerie Dominguez

(915) 851-0304 or vdominguez@epcountyesd2.org