



P.O. Box 683
Clint, Texas 79836

Phone (915) 851-0304 • Fax (915) 851-9000

Bid #2016-0125

West Valley Fire Station

Workout Room

- **Project Overview**

Contractor will need to furnish labor and materials for bid items listed below. A performance bond and permit included.

Metal Building 40FT. X 40FT.

- Concrete slab 6" with footing to engineers specs. ½" rebars at 16" O.C. B.W.
- 4000 PSI concrete, dirt work to raise floor 6" above existing ground level.
- 40FT. X 40FT. metal building with 12" end walls. 26.GA R-panel walls with all walls and ceiling fully insulated. Four (4) 6" skylight and four (4) 3FT X 5FT insulated windows in walls. Install liner panel on all exterior walls to protect insulation.
- Install 7 FT. X 8FT insulated roll-up garage door with electric door opener.
- Install electric wall plug at 10 FT spacing around exterior walls, at total of twelve (12). Four (4) tube fluorescent lights 8FT. in length. Lights must be LED and DLC compliant. Run panel from existing fire station
- Concrete floor needs to be covered with ½ rubber pad 4FT. X 6FT. on top of concrete.
- Mirrors on along one wall.
- Install one (1) 5 ton refrigerated A/C package unit and furnace. Mounted outside Vinton Rd. side on metal stand penetrating thru side wall. Center duct needed to supply building.
- One (1) 3FT. walk door

All work must have a manufactures warranty and one year labor warranty. All city permits must be included.

Please schedule a date and time to see the facility with Valerie Dominguez

(915) 851-0304 or vdominguez@epcountyesd2.org